



COMPONENTS INCLUDE:

2 STAGE VERTICAL SHEET PREFABRICATED WITH 1 3/8"x1 3/4" HARDWOOD / OAK POSTS (OR EQUAL DENSITY)
 ATTACHED FRONT WATER SEAL AND REAR SCOUR GUARD, SOD STAPLES, COMPRESSION TUBES FILLED WITH KILN DRIED PINE CHIPS (3) WITH COMPRESSION STAKES (6) AND (4) BONDING STRIPS WITH SCREWS

MAINTENANCE

ALL TEMPORARY EROSION, SEDIMENTATION, & POLLUTION CONTROL PRACTICES SHOULD BE INSPECTED DAILY. CONTRACTOR SHALL REMOVE SEDIMENT WHEN DEPOSITS REACH APPROXIMATELY ONE-HALF THE HEIGHT OF THE MATERIAL BARRIER. INSPECT DAILY FOR CUTS, ABRASIONS, AND PROPER INSTALLATION. REPLACE OR REPOSITION AS NECESSARY. REMOVE BUILDUP FROM HIGH VISIBILITY GREEN VELOCITY RESTRICTOR SHEET AS NEEDED BY TAPPING THE BACKSIDE WITH FLAT BOARD.

**SILT FENCE OUTLET
 MODEL # SFO-14**

ITEM ID: SILT FENCE OUTLET
 FABRIC MATERIAL: REFER TO SPEC
 SCALE: NOT TO SCALE
 LAST UPDATED: 2-12-2024